

## SMALL RUMINANTS

ITEM	DESCRIPTION	QTY	UNIT	RATE (EURO)	AMOUNT (EURO)
	<b>BILL NR. 1 - PRELIMINARIES</b>				
A	Mobilisation (Erect temporary site storage/ mess rooms, etc.)		Sum		
B	Performance Bond		Sum		
C	Insurance		Sum		
D	Safety, Fixed Charge		Sum		
E	Clean up after construction		Sum		
	<b>BILL NR. 1 - PRELIMINARIES</b>				
	Carried to Summary				

	<b>BILL NR. 2 - SUBSTRUCTURE</b>				
	<b>EARTHWORKS</b>				
A	Excavate to reduce level	1	ITEM		
	<b>E 10 - In-situ Concrete</b>				
B	Slab on grade 4" thick	11	CY		
	<b>E 20 - Formwork for In-situ Concrete</b>				
C	Sides of ground slab	5	SY		
	<b>E30 Reinforcement for In-situ Concrete</b>				
	<u>Mesh Fabric Reinforcement</u>				
D	BRC	103	SY		
	<b>BILL No. 2 - SUBSTRUCTURE</b>				
	Carried to Summary				

	<b>BILL NR. 3 - FRAME</b>				
	<b>E10 - In - situ Concrete</b>				
A	Column	1	CY		
B	Ring beam	2	CY		
	<b>E 20 - Formwork for In-situ Concrete</b>				
C	Column	21	SY		
D	Ring beam	30	SY		
	<b>E30 Reinforcement for In-situ Concrete</b>				
E	Column	188	LBS		
F	Ring beam	324	LBS		
	<b>BILL No. 3 - FRAME</b>				
	Carried to Summary				

## SMALL RUMINANTS

ITEM	DESCRIPTION	QTY	UNIT	RATE (EURO)	AMOUNT (EURO)
	<b>BILL NR. 4 - ROOF</b>				
	<b>G- STRUCTURAL TIMBER</b>				
	<u>Dress treated yellow pine</u>				
A	2" x 6" Ridge board	50	LF		
B	2" x 4" Rafters	682	LF		
C	1" x 4" Laths	475	LF		
D	1" x 6" Fascia Board	154	LF		
	<u>Unpainted galvanize roof sheeting:</u>				
E	Roof Coverings Pitch 30 Degrees	1755	SF		
F	Ridging	50	LF		
	<b>BILL NR. 4 - ROOF</b>				
	Carried to Summary				

	<b>BILL NR. 5 - BLOCKWORK</b>				
	<u>Hollow Concrete Blocks</u>				
A	Walls; 6" thick	58	SY		
	<b>BILL NR. 5 - BLOCKWORK</b>				
	Carried to Summary				

	<b>BILL NR. 6 - WINDOWS</b>				
A	A142 wire mesh in timber frame	111	SY		
	<b>BILL NR.6 - WINDOWS</b>				
	Carried to Summary				

	<b>BILL NR. 7 - DOORS</b>				
A	36" x 80" Timber panel door inclusive of frame and hardware	1	NR		
	<b>BILL NR. 7 - DOORS</b>				
	Carried to Summary				

## SMALL RUMINANTS

ITEM	DESCRIPTION	QTY	UNIT	RATE (EURO)	AMOUNT (EURO)
	<b>BILL NR. 8 - WALL FINISHES</b>				
	1/2" Cement / sand render				
A	Walls	114	SY		
	<b>BILL NR. 8 - WALL FINISHES</b>				
	Carried to Summary				

	<b>BILL NR. 9 - FLOOR FINISHES</b>				
A	Float concrete slab	103	SY		
	<b>BILL NR. 9 - FLOOR FINISHES</b>				
	Carried to Summary				

		<b>SUMMARY</b>			
<i>BILL</i>	<i>NR.</i>	<i>ELEMENT</i>			
<b>BILL NR.</b>	<b>1</b>	<b>PRELIMINARIES</b>		<b>EURO</b>	
<b>BILL NR.</b>	<b>2</b>	<b>SUBSTRUCTURE</b>		<b>EURO</b>	
<b>BILL NR.</b>	<b>3</b>	<b>FRAME</b>		<b>EURO</b>	
<b>BILL NR.</b>	<b>4</b>	<b>ROOF</b>		<b>EURO</b>	
<b>BILL NR.</b>	<b>5</b>	<b>BLOCKWORK</b>		<b>EURO</b>	
<b>BILL NR.</b>	<b>6</b>	<b>WINDOWS</b>		<b>EURO</b>	
<b>BILL NR.</b>	<b>7</b>	<b>DOORS</b>		<b>EURO</b>	
<b>BILL NR.</b>	<b>8</b>	<b>WALL FINISHES</b>		<b>EURO</b>	
<b>BILL NR.</b>	<b>9</b>	<b>FLOOR FINISHES</b>		<b>EURO</b>	
		<b>S U M M A R Y</b>			
		Carried to Form of Tender		<b>EURO</b>	