

SOW UNIT

ITEM	DESCRIPTION	QTY	UNIT	RATE (EURO)	AMOUNT (EURO)
	BILL NR. 1 - PRELIMINARIES				
A	Mobilisation (Erect temporary site storage/ mess rooms, etc.)		Sum		
B	Performance Bond		Sum		
C	Insurance		Sum		
D	Safety, Fixed Charge		Sum		
E	Clean up after construction		Sum		
	BILL NR. 1 - PRELIMINARIES				
	Carried to Summary				

	BILL NR. 2 - SUBSTRUCTURE				
	EARTHWORKS				
A	Excavate to reduce level	1	ITEM		
B	Sand blinding	103	SY		
C	Slab on grade 4" thick	11	CY		
	E 20 - Formwork for In-situ Concrete				
D	Sides of ground slab	5	SY		
	E30 Reinforcement for In-situ Concrete				
	<u>Mesh Fabric Reinforcement</u>				
E	BRC	103	SY		
	BILL No. 2 - SUBSTRUCTURE				
	Carried to Summary				

	BILL NR. 3 - FRAME				
	E10 - In - situ Concrete				
A	Column	1	CY		
B	Ring beam	2	CY		
	E 20 - Formwork for In-situ Concrete				
C	Column	21	SY		
D	Ring beam	30	SY		
	E30 Reinforcement for In-situ Concrete				
E	Column	188	LBS		
F	Ring beam	324	LBS		
	BILL No. 3 - FRAME				
	Carried to Summary				

SOW UNIT

ITEM	DESCRIPTION	QTY	UNIT	RATE (EURO)	AMOUNT (EURO)
	BILL NR. 4 - ROOF				
	G- STRUCTURAL TIMBER				
	<u>Dress treated yellow pine</u>				
A	2" x 6" Ridge board	50	LF		
B	2" x 4" Rafters	682	LF		
C	1" x 4" Laths	475	LF		
D	1" x 6" Fascia Board	154	LF		
	<u>Unpainted galvanize roof sheeting:</u>				
E	Roof Coverings Pitch 30 Degrees	1685	SF		
F	Ridging	50	LF		
	BILL NR. 4 - ROOF				
	Carried to Summary				

	BILL NR. 5 - BLOCKWORK				
	<u>Hollow Concrete Blocks</u>				
A	Walls; 6" thick	58	SY		
B	Walls; 4" thick	26	SY		
	BILL NR. 5 - BLOCKWORK				
	Carried to Summary				

	BILL NR. 6 - WINDOWS				
A	A142 wire mesh in timber frame	111	SY		
	BILL NR. 6 - WINDOWS				
	Carried to Summary				

	BILL NR. 7 - DOORS				
A	36" x 80" Timber panel door inclusive of frame and hardware	1	NR		
B	36" x 30" Metal gate	9	NR		
	BILL NR. 7 - DOORS				
	Carried to Summary				

SOW UNIT

	BILL NR. 8 - WALL FINISHES				
	1/2" Cement / sand render				
A	Walls	110	SY		
	BILL NR. 8 - WALL FINISHES				
	Carried to Summary				

	BILL NR. 9 - FLOOR FINISHES				
A	Float concrete slab	103	SY		
	BILL NR. 9 - FLOOR FINISHES				
	Carried to Summary				

ITEM	DESCRIPTION	QTY	UNIT	RATE (EURO)	AMOUNT (EURO)
	BILL NR. 10- PLUMBING INSTALLATION				
A	Cold Water Installation		Item		
B	Soil, waste and vent pipework		Item		
	BILL NO. 10 - PLUMBING INSTALLATION				
	Carried to Summary				

ITEM	DESCRIPTION	QTY	UNIT	RATE (EURO)	AMOUNT (EURO)
	BILL NR. 11 - EXTERNAL WORKS				
A	Soak away overall 10' long x 10' wide x 10' deep	1	No		
B	Soak away cover 2' long x 2' wide overall	1	No		
	Testing				
C	Allow for testing		Sum		
	BILL NO. 11 - EXTERNAL WORKS				
	Carried to Summary				

SOW UNIT

		SUMMARY			
<i>BILL</i>	<i>NR.</i>	<i>ELEMENT</i>			
BILL NR.	1	PRELIMINARIES		EURO	
BILL NR.	2	SUBSTRUCTURE		EURO	
BILL NR.	3	FRAME		EURO	
BILL NR.	4	ROOF		EURO	
BILL NR.	5	BLOCKWORK		EURO	
BILL NR.	6	WINDOWS		EURO	
BILL NR.	7	DOORS		EURO	
BILL NR.	8	WALL FINISHES		EURO	
BILL NR.	9	FLOOR FINISHES		EURO	
BILL NR.	10	PLUMBING INSTALLATION		EURO	
BILL NR.	10	EXTERNAL WORKS		EURO	
		SUMMARY			
		Carried to Form of Tender		EURO	