


Roof Construction:
2" x 4" Rafters @ 18" c/c. [d.t.p.p.]
1" x 4" Laths @ 24" c/c. [r.t.p.p.]
1" x 8" Fascia Board [d.t.p.p.]
Galvanize Sheathing



Roof Construction:
2" x 6" Rafters @ 24" c/c. [d.t.p.p.]
1" x 4" Laths @ 30" c/c. [r.t.p.p.]
1" x 8" Fascia Board [d.t.p.p.]
Galvanize Sheathing

H. Ralph Designs.
Sion Hill, Kingstown
St. Vincent & the Grenadines
Tel: 784-533-3999
e-mail: hralphdesigns@gmail.com

Client:

Central Planning Division
Kingstown
St. Vincent & the Grenadines

Project:

Proposed Packing Shed
at Banana Stations
[15'-0" x 15'-0"]

Drawg Title:

Packing Shed Roof Framing Plan

Project No:

HRD/004/15

Date:

March 2015

Scale:

1/4" : 1'0"

Drawn:

H. R.

Drawg No:

A-204