

Item #	Description	Quantity	Unit	Rate	Cost
	Packing Shed				
	<b><u>PRELIMINARIES</u></b>				
A	Mobilization (Site Office, Store Room, Work Bench, etc)	1	item		
B	SettingOut	1	item		
C	Clean up during works and after construction	1	item		
D	Transportation	1	item		
		<b><i>Sub- Total</i></b>			
	<b><u>SUBSTRUCTURE</u></b>				
1	<b>Earth Works &amp; Excavation</b>				
	Excavate trench for footing for foundation	11	cyd		
2	<b>Termite Treatment</b>				
	Termite treatment of excavated area and compound	14	Syd		
3	<b>Concrete/ Preparatory Works</b>				
	2" concrete blinding	1	cyd		
4	<b>Formwork</b>				
	1"x12"x16' R.P.P to vertical sides of foundation	100	ft		
5	<b>Reinforcement</b>				
	High tensile 1/2"" reinforcement bars to foundation pads	21	lbs		
	High tensile 1/2"" reinforcement bars to foundation tie beam	134	lbs		
	High tensile 3/8" bars or foundation tie beam stirrups	30	lbs		
6	<b>Foundation Walls</b>				
	8" concrete block foundation wall reinforced with every block filled with concrete	5	syd		
		<b><i>Sub- Total</i></b>			
	<b><u>SUPERSTRUCTURE</u></b>				
1	<b>Walls</b>				



