


FIXTURE SCHEDULE				
FIXTURE DESCRIPTION	CW	HW	SOIL	VENT
WM WASH MACHINE	1/2	1/2	1 1/2	1 1/2
WC WATER CLOSET	1	—	4	2
K.S KITCHEN SINK	1/2	1/2	1 1/2	1 1/4
LB LAVATORY BASIN	1/2	1/2	1 1/2	1 1/4
H.B HOSE BIBB	1/2	—	—	—
S.H SHOWER	1/2	1/2	1 1/2	1 1/4
F.D FLOOR DRAIN	—	—	3	—
U URINAL	3/4	—	1 1/2	1 1/2
WS WASH SINK	1/2	1/2	1 1/2	1 1/2
B.D BIDET	1/2	1/2	1 1/2	1 1/2


PLUMBING LEGEND

— GAS —	GAS SUPPLY
— COLD WATER SUPPLY	COLD WATER SUPPLY
— HOT WATER SUPPLY	HOT WATER SUPPLY
— HOT WATER RETURN	HOT WATER RETURN
— SOIL OR WASTE	SOIL OR WASTE
— VENT	VENT
— CLEAN-OUTS (WALL & FLOOR)	CLEAN-OUTS (WALL & FLOOR)
— GLOBE VALVE	GLOBE VALVE
— CHECK VALVE	CHECK VALVE
— PLUG VALVE	PLUG VALVE
— GATE VALVE	GATE VALVE
— DRAIN VALVE	DRAIN VALVE
CS	CLEANERS SINK
FD	FLOOR DRAIN
LB	LAVATORY BASIN
U	URINAL
WC	WATER CLOSET
FHR	FIRE HOSE REEL
FH	FIRE HYDRANT
DF	WATER COOLER
B	BATH TUB
SH	SHOWER
HB	HOSE BIBB
WM	WASHING MACHINE
DM	DRYER MACHINE
FFD	FUNNEL FLOOR DRAIN
WS	WASHING SINK
BD	BIDET



FOR TENDER

2012-09-18

No.	REVISION	DATE
This Drawing Is To Be Read With All Relevant Architectural, Structural And MEP Drawings. Report All Discrepancies, Omissions Or Errors To The Engineer. IF IN DOUBT-ASK.		
		
#1 Erin Terrace, Briffons Cross Road, St. Michael BB14002, Barbados, W.I.		
LEVERAGE CONSULTING ENGINEERS INC. HAS COPYRIGHT OF THIS DOCUMENT ©.		
architect		
MOULTON MAYERS ARCHITECTS		
job name		
MENTAL HEALTH CENTRE		
drawing title		
GROUND FLOOR SOIL/WASTE LAYOUT SHEET 2 OF 3		
drawn	des/chk	
R. Bartlett	R. Jordan	
scale	date	status
1/8"=1'-0"	JUN. '12	FOR TENDER
job no.	dwg. no.	rev.
120702	P-2	