## ELECTRICAL LEGEND

- 115V SINGLE RECEPTACLE (Wp DENOTES WEATHERPROOF) (GFCI DENOTES GROUND FAULT CIRCUIT INTERRUPTER) (GP DENOTES GENERAL PURPOSE OUTLETS)
- 115V DUPLEX RECEPTACLE (Wp DENOTES WEATHERPROOF) (GFCI DENOTES GROUND FAULT CIRCUIT INTERRUPTER) (GP DENOTES GENERAL PURPOSE OUTLETS) (RF DENOTES OUTLET THROUGH RF FILTER) (T DENOTES HOSPITAL-GRADE TAMPERPROOF RECEPTACLES)
- 220V SINGLE RECEPTACLE (Wp DENOTES WEATHERPROOF) (GFCI DENOTES GROUND FAULT CIRCUIT INTERRUPTER) (GP DENOTES GENERAL PURPOSE OUTLETS)
- 220V DUPLEX RECEPTACLE (Wp DENOTES WEATHERPROOF) (GFCI DENOTES GROUND FAULT CIRCUIT INTERRUPTER) (GP DENOTES GENERAL PURPOSE OUTLETS)
- 115V DUPLEX RECEPTACLE IN FLOOR BOX
- COMPUTER DRAW BOX
- TELEPHONE BOX
- ELECTRICAL DRAW BOX
- ISOLATOR.
- ELECTRICAL PANEL BOARD (Recessed)
- ELECTRICAL PANEL BOARD (Surface mounted)
- SINGLE POLE SWITCH (4'-6" AFFL) (2..DENOTES TWO WAY OPERATION)
- SINGLE POLE SWITCH (4'-6" AFFL)
- SWITCH WITH NEON INDICATOR (4'-6" AFFL)
- FAN SWITCH (4'-6" AFFL)
- AIR CONDITION SWITCH (4'-6" AFFL)
- DIMMER SWITCH (4'-6" AFFL)
- DENOTES LIGHTS ON THE SAME CIRCUIT BUT CONTROLLED BY DIFFERENT SWITCHES.
- HOME RUN TO PANEL.(NOTATION DENOTES PANEL AND CIRCUIT NUMBERS)
- ELECTRICAL CONDUIT/DUCT RUN.
- TELEPHONE CONDUIT/DUCT RUN.
- CABLE TRUNKING FOR DATA & POWER ACCESS
- TELEVISION
- TELEPHONE POINT IN 4x4 DRAW BOX WITH 2x4 REDUCING RING
- COMPUTER POINT IN 4x4 DRAW BOX WITH 2x4 REDUCING RING: B DENOTES BOX WITH BLANK PLATE, # DENOTES QUANTITY OF NETWORK POINTS, NO # DENOTES 1# NETWORK POINT
- TELEPHONE & COMPUTER POINT IN 4x4 DRAW BOX WITH 2x4 REDUCING RING; B DENOTES BOX WITH BLANK PLATE, # DENOTES QUANTITY OF COMPUTER/TELEPHONE POINTS, NO # DENOTES 1# COMPUTER & 1# TELEPHONE POINT.
- COMPUTER POINT IN FLOOR BOX
- CMH COMPUTER MANHOLE
- EMH ELECTRICAL MANHOLE
- SD SMOKE DETECTOR
- HD HEAT DETECTOR
- MD SECURITY MOTION DETECTOR
- FA FIRE ALARM HORN/STROBES
- FP BREAK GLASS STATION/PULL STATION
- 115V RECEPTACLE SUSPENDED FROM CEILING (HUBBELL KELLUM TWISTLOCK)
- ELECTRICAL CONTACTOR
- BS BELL SYSTEM DRAW BOX
- ELECTRICAL BELL
- HD HAND DRIER
- EMERGENCY LIGHTS
- COMBINATION EMERGENCY AND EXIT LIGHT
- EXIT EXIT LIGHT
- LOCKABLE EMERGENCY STOP BUTTON.
- AUDIO DRAW BOX
- EM FITTED WITH BODINE B50 EMERGENCY BALLAST
- CAMERA
- TRANSFORMER
- INTERCOM
- SWITCHED 115V SINGLE RECEPTACLE IN CEILING
- SWITCHED 115V DUPLEX RECEPTACLE IN CEILING
- SWITCHED 230V SINGLE RECEPTACLE IN CEILING
- SWITCHED 230V DUPLEX RECEPTACLE IN CEILING
- SPK SPEAKER DRAW BOX
- WD WIRELESS LIGHTING MOTION DETECTOR
- VC VOICE CONTROL DRAW BOX
- T THERMOSTAT
- KP SECURITY KEYPAD
- DC MAGNETIC DOOR LOCK
- JB JUNCTION BOX
- NP 4x4 WALL RECESSED DRAW BOX FOR NURSE CALL SINGLE PATIENT PULL STATION @ 50" AFFL
- ND NURSE CALL DUTY STATION @ 44" AFFL
- NM 12x12 WALL RECESSED DRAW BOX FOR NURSE CALL MASTER ANNUNCIATOR SYSTEM @ 44" AFFL
- NEC 4x4 WALL RECESSED DRAW BOX FOR NURSE CALL EMERGENCY STATION WITH PULL CORD @ 30" AFFL
- NCL NURSE CALL CORRIDOR CEILING MOUNTED DOME LIGHT




| No. | REVISION | DATE |
|---|---|---|

This Drawing Is To Be Read With All Relevant Architectural, Structural And MEP Drawings. Report All Discrepancies, Omissions Or Errors To The Engineer.

IF IN DOUBT-ASK


LEVERAGE CONSULTING ENGINEERS INC.

#1 Erin Terrace, Brittons Cross Road, St. Michael BB14002, Barbados, W.I.



LEVERAGE CONSULTING ENGINEERS INC. HAS COPYRIGHT OF THIS DOCUMENT ©.


architect

MOULTON MAYERS ARCHITECTS

job name

**MENTAL HEALTH CENTRE**

drawing title

**GROUND FLOOR POWER LAYOUT PART 2 OF 3**

FOR TENDER
2012-09-18

| | | |
|---|---|---|
| drawn *Javid B.* | des/chk *R. Foster* | |
| scale 1/8"=1'-0" | date JUN. '12 | status TENDER |
| job no. 120702 | dwg. no. E-3 | rev. |